

**REQUEST FOR PROPOSAL**  
**Ogden Airport Fiber Ring Connection**  
(Conduit Amendment)



Prepared by Crystal Griffin, I.T. Project Manager for Ogden City

April 7, 2021

Additional conduit specification update and information on conduit for this project. The “Conduit 1.25” needs to be changed to a “1D Conduit” that follows all “UDOT Standard Drawing AT 6” (see [link](#) for more details).

*More Information*

**1D CONDUIT, Bid Item 1107**

1. Measured per linear foot of 1D conduit (FT).
2. Payment includes all labor, equipment, directional bore installation, conduit, detectable pull tape, flowable fill, and materials necessary for finished conduit in place as detailed in the plans, in the UDOT Standard Drawing AT 6, and UDOT

